



## DETAILED BILL OF QUANTITIES

Project No.: 0  
 Project: Construction of new registration center - Lapida  
 Item: Civil works for fence , gates and Ground levelling  
 Ref.: Drawings

Date: Decemebr 07/2015

All prices in EUR

Pos.	Description of Work/Items	Unit	Quantity	Unit Cost	Total Cost
<b>1. Levelling of existing ground</b>					
a	Provide quality base course layer (abc) including necessary drain lines on the existing base course layer and level providing proper slope to drain the rain water smoothly without any water stagnation in side the waiting area. ( The Contractor is advised to visit the site prior to the pricing)	sqm	11,000		
<b>2. Notes</b>					
a	<i>Note : Rates shall include for (a) levelling bottem of trenches and keeping sides plumb; (b) backfilling of column pits, foundation trenches &amp;etc.,</i>				
<b>4. New security wall fence</b>					
a	Supply, installation and commissioning of a new 2m high security wall fence including: steel structure, installation of steel 75mm dis G.I posts, 5mm tk G,I chain link mesh, as directed by Engineering-in-Charge as a completed job.	l.m	220	\$0	
<b>5. Foundation work for the steel fence</b>					
a	Excavate trench for R.C.C column footings as per the detail drawings. All excess materials should take away from the site and dump in approved locations by the municipalty.	m3	8		
b	Back fill the excavated foundation with imported quality soil and compact well.	m3	0		
c	Note: Rate shall include for (a) all necessary form work for forming squre colomn shafts placing, vibrating, curing etc. (b) unless otherwise stated include for all reinforcement.				
d	Mass concrete 1:2:4 foundation bases for steel G.I pipe columns.	m3	8		
<b>Subtotal general</b>					