

Financial Bidding Form BOQ Ticketing Booth

All prices in EUR

Item	Description of Work	Unit	Qty	Rate	Amount
1.0	<u>Preliminaries</u>				
1.3	Allow for temporary water and electrical etc.	Item	1		
2.0	<u>EXCAVATOR</u>				
2.1	Excavate for wall foundations & column footings staircase foundation etc., soil part return and cart away surplus as directed.	cubes	4.5		
2.2	Filling under floors with selected soil materials in layers of 6" and free from all vegetable materials watered & rammed well as directed.	cubes	1.4112		
3.0	<u>CONCRETOR</u>				
3.1	2" thick cement concrete in column foundations in 1:3:6 (1")	sqrs.	78.5		
	<u>Reinforced cement concrete 1:2:4(3/4) in the following items.</u>				
3.2	R.C.C. in column bases R/F with 10mm tor steel bars 8 nos each direction	cubes	0.792		
Item	Description of Work				
5.0	<u>Wall Work</u>				
5.1	4 CM ALUMINUM POLYURETHANE PANELS	Sqrs.	64		
5.2	10X10 CM IRON FRAME STRUCTURE	Meters	37.6		
6.0	<u>FLOOR</u>				
6.1	WOODEN FLOOR	Sqrs.	10		
7.0	<u>DOOR WINDOW</u>				
7.1	DOOR ALUNIMUN	Sqrs.			
7.2	WINDOW ALUMINUM	Sqrs.			
8.0	<u>FURNITURE</u>				
8.1	Chair	Items	1		
8.2	Desk (wooden desk 1,6 x 0,5 meters)	Items	1		